


# CAVITE STATE UNIVERSITY

## **BIDS AND AWARDS COMMITTEE** (INFRASTRUCTURE PROJECTS)

### **SUPPLEMENTAL / BID BULLETIN NO. 1**

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Construction of CVMBS Academic Building (CvSU-BAC-INFRA-23-043)** with an **ABC** of **16,980,000.00**:

1. Site inspection is a must. Verify actual condition of site.
2. Site temporary enclosure may be sack or any suitable materials that may enclose the workplace.
3. There are additional plans to increase detailing.
  - a. 4 pages Architectural plans
  - b. 2 pages Structural plans
  - c. 5 pages Electrical plans
4. The architectural plan shows the L- shaped canopy on grids A-B/1-2.
5. There are revisions for enhancement in trusses as shown in additional plans.
  - a. vertical and diagonal secondary web members must be installed.
  - b. Use 1.5 mm thick CEE purlins spaced at 0.53m on center as supported by web members.
6. The electrical plans were enhanced.
  - a. The location of switches was shown.
  - b. Feeder line is to be installed from MDP to secondary post up to the proposed power source which is adjacent to the secondary post.
  - c. Included in the additional plans is the secondary post.
7. For plumbing works:
  - a. Installation of water meter.
  - b. Floor drains shall use PVC orange pipes 2" diameter.
  - c. All comfort room fixtures shall be colored (tank type water closets, counter top type lavatories and wall hung type lavatories).
8. Ceiling boards shall be fiber cement boards on metal furring complete with carrying and fastening accessories.
9. For miscellaneous works:
  - a. Use lever type heavy duty knobs.
  - b. PVC accordion partition walls on second and third floors shall be installed on grids C,D & E / 2-4.
10. Fire protection:
  - a. Dry stand pipes shall use GI pipes and fittings S-40.
  - b. The fire alarm control panel must be addressable type.
  - c. Fire hose length shall be at least 30 meters.



# CAVITE STATE UNIVERSITY

## GENERAL NOTES:

1. *This bid bulletin does not cancel the information given in the scope of work of the Bill of Quantities but adds clarification to it. Please attach this added information/ bid bulletin to the BOQ and include in the financial envelope.*
2. The colors, types and specifications of all fixtures and materials to be used on site should be consulted to the inspector or end-user for approval. As possible, let the end-user or the inspector sign the approved sample. Further, consult the plan and the scope of work for the extent of tasks of the contract.
3. In the event that discrepancies on plans and scope of work occur, generally, the scope of work prevails. Further, whichever is advantageous to the government is given priority.
4. For concrete works: provide ready mixed concrete of specified strength.
5. Materials to be used on site must be subjected to material testing which will be charged to the contractor.
- 6.