



CAVITE STATE UNIVERSITY

BIDS AND AWARDS COMMITTEE (INFRASTRUCTURE PROJECTS)

SUPPLEMENTAL / BID BULLETIN NO. 1

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Construction of Parking Space and Electrical Feeder Line for Bahay Alumni (CvSU-BAC-INFRA-24-002)** with an ABC of **1,406,479.46**:

1. Site inspection is a must. Verify actual condition of site.
2. Site temporary enclosure may be sack or any suitable materials that may enclose the workplace.
3. There is an additional plan on electrical (feeder line) to increase detailing.
4. Provide clearing of the area for parking.
5. For Item IV. Concrete Pavement
 - a. Provide necessary formworks to complete the works.
 - b. Parking space shall be 0.15 meters thick; 23 meters long and 10.10 meters wide (see plan).
 - c. Use ready mixed concrete with 3500 psi strength @ 28 days.
 - d. Provide 10 mm 0 deformed bar for reinforcement spaced at 0.40 meters bothways.
 - e. See plans/consult the end user and project inspector for further extent of works.
6. Item V Miscellaneous Works include the electrical works and the chipping/retouching/repainting works of the area affected by the installation of conduit pipe raceway up to the wall of existing Gymnasium building.
7. The issued plan of ramps for the alumni building may be disregarded since that is not part of the scope of this project.

