IX	PLUMBING WORKS (Pesos _____ _____ _____ and _____ centavos)				
X	FIRE PROTECTION WORKS (Pesos _____ _____ _____ and _____ centavos)				
XI	PAINTING WORKS (Pesos _____ _____ _____ and _____ centavos)				
	GRAND TOTAL				_____

Write grand total 7,151

SCOPE OF WORK:

A. **IMPROVEMENT OF COLLEGE OF NURSING TO INCREASE CARRYING CAPACITY - 2nd POSTING**

GENERAL NOTES:

1. The project should be finished in 240 calendar days.
2. Actual site inspection is a must.Verify actual condition of site.
3. This set of specifications shall govern the methods of construction and the kinds of materials to be used for the proposed project shown in the plans and detailed drawings.
4. All parts of the construction shall be finished with first class workmanship, to the fullest talent and meaning of the plans and these specifications, and to the entire satisfaction of the project inspector and the end-user.

B. Technical Description

I. Preliminary Works and Earthworks

A. Mobilization/Demobilization

Provide the following:

1. Billboard with project information
2. Bunkhouse with temporary office
3. Temporary comfort rooms
4. Site temporary enclosure may be blue sack or any suitable materials that may enclose the workplace.
5. It includes cleaning up of site, clearing, hauling and disposal of waste and construction debris.
6.

8. In case of failure of test cylinders to meet the specified strengths, the Contractor shall at his expense obtain concrete core samples from the poured concrete and the compressive strength of same be taken by a competent testing authority to determine the conclusive strength and integrity of the concrete poured.

B. Steel reinforcement
   1. Provide 10 mm Ø deformed bars at 0.30m on center both ways for slab on fill at ground floor.
   2. Use deformed bar grade 40.
   3. Provide necessary tools and equipment needed for steel works.
   4. See plan for details and extent of work.
   5. The contractor shall furnish 2 copies of the manufacturer's certificate of mill tests of all reinforcing steel. The contractor shall at his own expense employ an approved testing laboratory which shall conduct testing of all reinforcement sizes of each bulk under the supervision of the project inspector.

C. Waterproofing works
   1. Waterproofing for all comfort rooms shall be included.

III. Masonry Works

A. CHB laying
   1. Installation of CHB reinforced with 10 mm Ø deformed bar spaced at 0.60 m. on center every three layers.
      a.

2. Supply and installation of copper conductor wires and PVC conduit/junction box/utility

c. Use 20 mm. Ø for inside of comfort rooms.
d. Provide gate valve for every comfort room.

2. Tapping to the source is included.
3. No pipe should be embedded without testing it to leak.

B. Sewer Line

1. Adopt PVC heavy duty orange pipes and fittings (Sanimold type with O-ring or its equivalent) for ventilation, downspout and the whole sewer line system including the septic vault fittings.
    a. Use R.C.P. for storm drainage.
    b. Use 4" Ø for sewer lines and down spout.
    c. Use 2"Ø and 3" Ø for lavatory.
2. Provide storm drainage system for the whole building (Grids 1 & 6). Downspout should be installed in every column.
   Note: For Grid 1, connect the downspout from the gutter to the existing downspout at fourth floor.
3. Provide two units septic tank.
4. Provide catch basin with RCP pipes.

C. Fixtures

Supply and Installation of the following:

1. 5 pcs. heavy duty faucet (stainless).
2. 8 units of heavy duty spray bidet for every cubicle of comfort room.
3. 8 sets of Colored Water Closet (tank type)
4. 5 sets of under-the-counter lavatories complete with all accessories
5. 2 units concrete counter finished with granite tiles
6. 3 sets of Colored Urinal with phenolic partition with stainless brackets.
7. 11 pcs. Floor drain strainer (brass)
8. 1 pc. Mirror (2.0 m. x 1.0 m. x 6.0 mm.)
9. 1 pc. Mirror (0.8 m. x 1.0 m. x 6.0 mm.)
   Note: All fixtures must be HCG, American Std, or approved equivalent complete with all accessories.

X. Fire Protection Works

Supply and Installation of dry standpipe with fire hose and cabinet:

1. 10 - units firehose, (50 mtrs.) with cabinet
2. Dry stand pipe 3" with siamese fitting

XI. Painting Works

The whole new structure should be painted (both exterior & interior) including doors.

A. Wood

1. Apply one coat of flatwall enamel white. Allow to dry overnight.
2. Repair minor surface imperfection with glazing putty. Let dry then sand.
3. Apply at least two coats of Quick Dry Enamel in the desired color. Allow an overnight intercoating interval.

B. Metal

1. Apply epoxy primer by brush or spray. Allow to dry for 24 hours. Apply suitable putty on imperfections.
2. Apply at least two coats of Quick Dry Enamel in the desired color.

C. Concrete

1. Treat the surface with concrete neutralizer. Mix one part with 16 parts water by volume.
2. Apply skim coat as primer. Repair minor surface imperfections with a suitable putty. Let dry, then sand.
3. Apply at least two coats of colored dirt resistant semi gloss latex paint (factory mixed).
   Note: Color of paint will depend upon the preference of the end-user. Paints and its accessories should be BOYSEN or approved equal.

C. Contractor of the said project must provide an as-built plan of the project at the end of the contract as a requirement for the release of their final billing.

D. For color/types of any fixtures or materials to be used on site, consult the end-user and the

inspector for approval. Consult the plan and the scope of work for the extent of tasks of the contract. If possible, let the end-user sign your sample as proof of approval.

E. The plans, detailed drawings and these specifications shall be considered as complementing each other, so that what is mentioned or shown in one, although not mentioned or shown in the other, shall be considered as appearing on both. **In case of conflict between the two, generally, the scope of work prevails.**

F. Resident site engineer is a mus1 72.744 g0 G**[**I)-4(n)13()13(r)-3(a)13(w(84 732.94 Tm0 g0 Tm0 g8G**[**I)3